

総 括 表 (No. 1)

工事区分 (レベル1)	工 種 (レベル2)	種 別 (レベル3)	細 別 (レベル4)	規 格 (レベル5)	単位	数量	
〔市役所線側溝設置等工事〕							
	排水構造物工						
		作業土工					
			床掘り	土砂	m ³	570	
			埋戻し	最大埋戻し幅1m以上4m未満	m ³	210	
			〃	最大埋戻し幅1m未満	m ³	40	
			路床盛土	B<2.5	m ³	160	
			〃	2.5≤B<4.0	m ³	20	
			路体盛土	B<2.5	m ³	10	
			基面整正	土砂	m ²	160	
			土砂等運搬		m ³	80	
			処分費		m ³	80	
					t	140	
		側溝工					
			自由勾配側溝				
			自由勾配側溝	1000kg/個以下	m	170	
			〃 〃	1000kg/個以上2000kg/個以下	m	42	
			自由勾配側溝(縦断用)	W300×h400—L2000	個	1	
					m	2.0	
			〃 〃	〃 〃 —L1000	個	1	
					m	1.0	
			〃 〃	〃 〃 —L1272	個	1	
					m	1.3	
			〃 〃	W300×h500—L2000	個	29	
					m	58.0	

総 括 表 (No. 2)

工事区分 (レベル1)	工 種 (レベル2)	種 別 (レベル3)	細 別 (レベル4)	規 格 (レベル5)	単位	数量	
			自由勾配側溝(縦断用)	W300×h600－L2000	個	11	
					m	22.0	
			〃 〃	〃 〃 －L1407	個	1	
					m	1.4	
			〃 〃	〃 〃 －L1329	個	1	
					m	1.3	
			〃 〃	〃 〃 －L1555	個	1	
					m	1.6	
			〃 〃	W300×h700－L2000	個	2	
					m	4.0	
			〃 〃	W300×h800－L2000	個	8	
					m	16.0	
			〃 〃	W300×h900－L2000	個	4	
					m	8.0	
			〃 〃	〃 〃 －L1000	個	5	
					m	5.0	
			〃 〃	〃 〃 －L1144	個	1	
					m	1.1	
			〃 〃	〃 〃 －L1074	個	1	
					m	1.1	
			〃 〃	〃 〃 －L1012	個	2	
					m	2.0	
			〃 〃	〃 〃 －L1006	個	1	
					m	1.0	

総 括 表 (No. 3)

工事区分 (レベル1)	工 種 (レベル2)	種 別 (レベル3)	細 別 (レベル4)	規 格 (レベル5)	単位	数量	
			自由勾配側溝(縦断用)	W300×h900－L1007	個	5	
					m	5.0	
			〃 〃	〃 〃 －L1012	個	2	
					m	2.0	
			〃 〃	W300×h1000－L2000	個	13	
					m	26.0	
			〃 〃	〃 〃 －L1000	個	2	
					m	2.0	
			〃 〃	〃 〃 －L1307	個	1	
					m	1.3	
			〃 〃	W300×h1100－L2000	個	18	
					m	36.0	
			自由勾配側溝(横断用)	W300×h1000－L2000	個	3	
					m	6.0	
			〃 〃	〃 〃 －L1000	個	4	
					m	4.0	
			〃 〃	〃 〃 －L1462	個	1	
					m	1.5	
			〃 〃	〃 〃 －L1437	個	1	
					m	1.4	

総 括 表 (No. 4)

工事区分 (レベル1)	工 種 (レベル2)	種 別 (レベル3)	細 別 (レベル4)	規 格 (レベル5)	単位	数量	
			コンクリート蓋	B300-L2000	枚	70	
			〃 〃	〃 -L1000	枚	8	
			〃 〃	〃 -L1272	枚	1	
			〃 〃	〃 -L1144	枚	1	
			〃 〃	〃 -L1307	枚	1	
			〃 〃	〃 -L1407	枚	1	
			〃 〃	〃 -L1329	枚	1	
			〃 〃	〃 -L1555	枚	1	
			〃 〃	〃 -L1074	枚	1	
			〃 〃	〃 -L1012	枚	2	
			〃 〃	〃 -L1006	枚	1	
			〃 〃	〃 -L1007	枚	5	
			〃 〃	〃 -L1012	枚	2	
			コンクリート蓋(管理孔用)	B300-L2000	枚	16	
			グレーチング蓋	B300-L1000、横断用	枚	12	
			〃 〃	〃 -L 462、 〃	枚	1	
			〃 〃	〃 -L 437、 〃	枚	1	
			インパートコンクリート	18N/mm2以上	m ³	8	
			基礎コンクリート	18N/mm2以上	m ³	1	
			同上 型枠	均し	m ²	3	
			基礎碎石	RC-30, t=100	m ²	37	
			〃	RC-40, t=150	m ²	68	
			〃	〃 , t=200	m ²	22	

総 括 表 (No. 5)

工事区分 (レベル1)	工 種 (レベル2)	種 別 (レベル3)	細 別 (レベル4)	規 格 (レベル5)	単位	数量	
			1号U型側溝				
			コンクリート	18N/mm2以上	m ³	1	
			型枠	一般型枠	m ²	15	
			基礎碎石	RC-40, t=150	m ²	5	
			目地材	瀝青質目地材 t=10mm	m ²	0.1	
			コンクリート蓋	C2-B300	枚	14	
			管渠工				
			1号管渠	Co台付き管 φ 300	m	34	
			2号管渠	〃 φ 400	m	8	
		集水桝工					
			3号街渠桝	400×600×950	基	1	
			(Co規格=18-8-25、1箇所当りCo量=0.401m3、 Co打設工法=人力、養生工=一般)				
			4号街渠桝	400×600×850	基	1	
			(Co規格=18-8-25、1箇所当りCo量=0.375m3、 Co打設工法=人力、養生工=一般)				
			5号街渠桝	400×600×950	基	1	
			(Co規格=18-8-25、1箇所当りCo量=0.384m3、 Co打設工法=人力、養生工=一般)				
			1-2号集水桝	プレキャスト桝	基	2	
			1-3号集水桝	〃	基	1	
			3-2号集水桝	〃	基	4	
			3-3号集水桝	〃	基	2	
		閉塞工					
			モルタル	1 : 3	m ³	1	

総 括 表 (No. 6)



工事区分 (レベル1)	工 種 (レベル2)	種 別 (レベル3)	細 別 (レベル4)	規 格 (レベル5)	単位	数量	
		舗装工					
			1号車道舗装 (現況復旧)				
			表層	再生密粒度As, t=50	m ²	353	
			下層路盤	RC-30, t=100	m ²	353	
	構造物撤去工						
		作業土工					
			床掘り	土砂	m ³	130	
			埋戻し	最大埋戻し幅1m以上4m未満	m ³	40	
			路床盛土	B<2.5	m ³	70	
			〃	2.5≤B<4.0	m ³	10	
			路体盛土	B<2.5	m ³	10	
		構造物撤去工					
			鋼製蓋 撤去	500×500	枚	3	
			マンホール蓋 撤去	φ 500	枚	1	
			〃	φ 1000	枚	1	
		構造物とりこわし工					
			コンクリート取壊し	無筋	m ³	30	
			〃	鉄筋	m ³	9	
			As舗装版 取壊し	t=50	m ²	341	
			As舗装版 切断	t=50	m	358	
			殻運搬				
			Co殻	無筋	m ³	30	
			〃	鉄筋	m ³	9	
			As殻		m ³	17	
			処分費	Co殻+As殻	t	133	

残 土 集 計 表								
工種	種別	名称	土質	f	設計数量	N	C	備考
発生土								
	切土				0	0	0	発生比率 C
			土砂	0.9	0	0	0	1.00
	床掘残土				80	80		
			土砂	0.9	80	80	70	
必要土								
	本体盛土							
		切土流用			0		0	
			土砂	0.9	0	0	0	0×1.00
残土処理								
	残土				80	80		
			土砂	0.9	80	80		80 - 0

床掘残土集計表							
種別	土質	f	床掘		埋戻		備考
			N	C	N	C	
			700	630		560	
作業土工	土砂	0.9	700	630		560	630/630=1.00
			発生土	必要土			
排水工	床掘り	土 砂	570				
	埋戻し			250			
	路床盛土			170			
	路体盛土			10			
撤去工	床掘り	土 砂	130				
	埋戻し			40			
	路床盛土			80			
	路体盛土			10			
		計	700	560			
計				630		560	70+0=70(残土)
	土砂			630		560	630-560=70

排水工 作業土工 集計

種 別：作業土工
ブロック：
区 分：

細別／規格	算 式 ／ 図	数 量
床掘り 土砂		567.2 m3
本線右側	土積計算書より	= 364.0
本線左側	〃	= 106.2
1号U型側溝	No. 6+8 左側 1.04㎡×6.8m	= 7.1
1号管渠	No. 3+16 横断部 1.33㎡×10.7m	= 14.2
〃	No. 5+16.5 横断部 1.98㎡×(13.4m+13.8m)	= 53.9
2号管渠	No. 1 横断部 2.42㎡×9.0m	= 21.8
埋戻し		
最大埋戻し幅1m以上4m未満		205.3 m3
本線右側	土積計算書より	= 205.3
最大埋戻し幅1m未満		41.4 m3
本線右側	土積計算書より	= 6.0
本線左側	〃	= 35.4
路床盛土 B<2.5		155.6 m3
本線右側	土積計算書より	= 66.7
本線左側	〃	= 35.4
1号U型側溝	No. 6+8 左側 0.54㎡×6.8m	= 3.7
1号管渠	No. 3+16 横断部 0.92㎡×10.7m	= 9.8
〃	No. 5+16.5 横断部 1.47㎡×(13.4m+13.8m)	= 40.0
路床盛土 2.5≤B<4.0		15.8 m3
2号管渠	No. 1 横断部 1.76㎡×9.0m	= 15.8
路体盛土 B<2.5		5.6 m3
本線右側	土積計算書より	= 5.6
1号管渠 No. 3+16.0横断部  床掘り 1.33 路床盛土 0.92 1号管渠 No. 5+16.5横断部  床掘り 1.98 路床盛土 1.47 2号管渠 No. 1横断部  床掘り 2.42 路床盛土 1.76 1号U型側溝 No. 6+8付近  床掘り 1.04 路床盛土 0.54		

排水工 作業土工 集計

種 別：作業土工
ブロック：
区 分：

細別／規格	算 式 ／ 図				数 量
基面整正 土砂					159.5 m2
	自由勾配側溝	基礎碎石計算より	$37.36\text{m}^2 + 68.28\text{m}^2 + 21.60\text{m}^2$	= 127.2	
	1号U型側溝	$0.70\text{m}^2 \times 6.79\text{m}$		= 4.8	
	1号管渠	$0.47\text{m}^2 \times 34.05\text{m}$		= 16.0	
	2号管渠	$0.55\text{m}^2 \times 7.60\text{m}$		= 4.2	
	3～5号街渠柵	$0.80\text{m}^2 \times 3\text{基}$		= 2.4	
	1号集水柵	$0.36\text{m}^2 \times (2\text{基} + 1\text{基})$		= 1.1	
	3号集水柵	$0.64\text{m}^2 \times (4\text{基} + 2\text{基})$		= 3.8	

排水工 作業土工

測 点	点間距離 (m)	床掘り						埋戻し			埋戻し			備 考
		土砂						最大埋戻し幅1m以上4m未満			最大埋戻し幅1m未満			
		断 面	平 均	数 量				断 面	平 均	数 量	断 面	平 均	数 量	
〔右側〕														
No. 1 + 2.350	—	2.7	—	—				1.3	—	—				No. 2流用
No. 2	17.650	2.7	2.70	47.7				1.3	1.30	22.9				
No. 3	20.000	2.6	2.65	53.0				1.4	1.35	27.0				
No. 4	20.000	3.1	2.85	57.0				1.2	1.30	26.0				
No. 5	<u>18.730</u>	2.9	3.00	56.2				2.6	1.90	35.6				
No. 6	<u>15.796</u>	3.4	3.15	49.8				2.3	2.45	38.7				
No. 7	<u>17.309</u>	3.0	3.20	55.4				2.0	2.15	37.2	0.0	—	—	
No. 7 + 17.955	<u>17.867</u>	1.2	2.10	37.5				0.0	1.00	17.9	0.4	0.20	3.6	No. 8流用
No. 8	<u>2.306</u>	1.2	1.20	2.8							0.4	0.40	0.9	
No. 8 + 3.367	<u>3.796</u>	1.2	1.20	4.6							0.4	0.40	1.5	No. 8流用
	※下線付き点間距離は平面図CAD計測													
合 計	m 133.454			m3 364.0						m3 205.3			m3 6.0	

排水工 作業土工

測 点	点間距離 (m)	路床盛土						路体盛土						備 考
		B<2.5m						B<2.5m						
		断 面	平 均	数 量				断 面	平 均	数 量				
〔右側〕														
No. 1 + 2.350	—	0.9	—	—				0.1	—	—				No. 2流用
No. 2	17.650	0.9	0.90	15.9				0.1	0.10	1.8				
No. 3	20.000	0.8	0.85	17.0				0.1	0.10	2.0				
No. 4	20.000	1.1	0.95	19.0				0.03	0.07	1.4				
No. 5	<u>18.730</u>	0.0	0.55	10.3				0.0	0.02	0.4				
No. 6	<u>15.796</u>	0.0	0.00	0.0										
No. 7	<u>17.309</u>	0.0	0.00	0.0										
No. 7 + 17.955	<u>17.867</u>	0.3	0.15	2.7										No. 8流用
No. 8	<u>2.306</u>	0.3	0.30	0.7										
No. 8 + 3.367	<u>3.796</u>	0.3	0.30	1.1										No. 8流用
	※下線付き点間距離は平面図CAD計測													
合 計	m 133.454			m3 66.7						m3 5.6				

排水工 作業土工

測 点	点間距離 (m)	床掘り						埋戻し			路床盛土			備 考
		土砂						最大埋戻し幅1m未満			B<2.5m			
		断 面	平 均	数 量				断 面	平 均	数 量	断 面	平 均	数 量	
〔左側〕														
No. 1 + 0.350	—	1.5	—	—				0.5	—	—	0.5	—	—	No.2流用
No. 2	19.650	1.5	1.50	29.5				0.5	0.50	9.8	0.5	0.50	9.8	
No. 3	20.000	1.2	1.35	27.0				0.4	0.45	9.0	0.4	0.45	9.0	
No. 4	20.000	1.2	1.20	24.0				0.4	0.40	8.0	0.4	0.40	8.0	
No. 5	20.000	1.2	1.20	24.0				0.4	0.40	8.0	0.4	0.40	8.0	
No. 5 + 1.376	1.376	1.2	1.20	1.7				0.4	0.40	0.6	0.4	0.40	0.6	No.5流用
合 計	m 81.026			m3 106.2						m3 35.4			m3 35.4	

排水構造物工 集計

種 別：排水構造物工
 ブロック：
 区 分：

細別／規格	算 式 / 図	数 量
自由勾配側溝		
右側	No. 1+ 2.35～No. 3+15.66 L= 53.31	
〃	No. 3+16.36～No. 5+15.97 L= 34.97	
〃	No. 5+16.90～No. 6+ 3.51 L= 5.17	
〃	No. 6+ 4.38～No. 7+19.14 L= 32.96	
〃	No. 7+19.58～No. 8+ 3.36 L= 4.27	
左側	No. 1+ 0.35～No. 3+15.76 L= 55.41	
〃	No. 3+ 16.26～No. 5+ 1.38 L= 26.00	
	計 212.09m	
	1000kg/個を超え2000kg/個以下 「側溝数量表」より	
	FNV1 W300×h1100 2.00m×18個 = 36.00	
	FNV2 W300×h1000 2.00m× 3個 = 6.00	
	計 42.00m	
[1.0式あたり]		
自由勾配側溝		
1000kg/個以下	212.09m－42.00m	170.09 m
1000kg/個以上2000kg/個以下	上記 計算より	42.00 m
自由勾配側溝 本体		
FNV1同等品	W300×h400－L2000 1.0 個	
	〃 〃 －L1000 短品 1.0 個	
	〃 〃 －L1272 〃 1.0 個	
	W300×h500－L2000 29.0 個	
	W300×h600－L2000 11.0 個	
	〃 〃 －L1407 短品 1.0 個	
	〃 〃 －L1329 片斜切 1.0 個	
	〃 〃 －L1555 〃 1.0 個	
	W300×h700－L2000 2.0 個	
	W300×h800－L2000 8.0 個	
	W300×h900－L2000 4.0 個	
	〃 〃 －L1000 短品 5.0 個	
	〃 〃 －L1144 〃 1.0 個	
	〃 〃 －L1074 片斜切 1.0 個	
	〃 〃 －L1012 〃 2.0 個	
	〃 〃 －L1006 〃 1.0 個	
	〃 〃 －L1007 〃 5.0 個	
	〃 〃 －L1012 両斜切 2.0 個	
	W300×h1000－L2000 13.0 個	
	〃 〃 －L1000 短品 2.0 個	
	〃 〃 －L1307 〃 1.0 個	
	W300×h1100－L2000 18.0 個	
FNV2同等品	W300×h1000－L2000 3.0 個	
	〃 〃 －L1000 短品 4.0 個	
	〃 〃 －L1462 片斜切 1.0 個	
	〃 〃 －L1437 〃 1.0 個	

排水構造物工 集計

種 別：排水構造物工
 ブロック：
 区 分：

細別／規格	算 式 ／ 図	数 量
コンクリート蓋		
F0sE1同等品	B300－L2000	70.0 枚
	〃 －L1000 短品	8.0 枚
	〃 －L1272 〃	1.0 枚
	〃 －L1144 〃	1.0 枚
	〃 －L1307 〃	1.0 枚
	〃 －L1407 〃	1.0 枚
	〃 －L1329 片斜切	1.0 枚
	〃 －L1555 〃	1.0 枚
	〃 －L1074 〃	1.0 枚
	〃 －L1012 〃	2.0 枚
	〃 －L1006 〃	1.0 枚
	〃 －L1007 〃	5.0 枚
	〃 －L1012 両斜切	2.0 枚
F0sEG1同等品	B300－L2000	16.0 枚
グレーチング(横断用)	B300－L1000	12.0 枚
	〃 －L 462	1.0 枚
	〃 －L 437	1.0 枚
インバートコンクリート		
18N/mm2以上	別紙 計算書より	7.6 m3
基礎コンクリート		
18N/mm2以上		0.774 m3
W300	$0.600 \times 0.100 \times (4.000\text{m} + 8.899\text{m})$	$= 0.774$
同上 型枠		
均し	$0.10 \times 2\text{面} \times (4.00\text{m} + 8.899\text{m})$	$= 2.580$ 2.58 m2
基礎碎石		
RC-30, t=100	(～h500)	37.36 m2
右側	W300 $0.60 \times 4.272\text{m}$	$= 2.563$
左側	W300 $0.60 \times 58.000\text{m}$	$= 34.800$
RC-40, t=150	(h600～h1000)	68.28 m2
右側	W300 $0.60 \times (2.884\text{m} + 4.00\text{m} + 16.00\text{m} + 10.074\text{m} + 5.168\text{m} + 12.065\text{m} + 8.899\text{m} + 14.00\text{m} + 7.307\text{m} + 6.00\text{m} + 4.00\text{m})$	$= 54.238$
左側	W300 $0.60 \times 23.407\text{m}$	$= 14.044$
RC-40, t=200	(h1100～)	21.60 m2
右側	W300 $0.60 \times 36.00\text{m}$	$= 21.600$

排水構造物工 集計

種 別：排水構造物工
 ブロック：
 区 分：

細別／規格	算 式 ／ 図				数 量
1号管渠					
Co台付き管 φ 300					34.05 m
右側	No. 3 + 16.01付近	4号街渠桝～3-3号集水桝	L= 1.85		
〃	No. 5 + 16.50付近	3号街渠桝～3-3号集水桝	L= 1.85		
横断	No. 3 + 16.01付近	1-2号集水桝～4号街渠桝	L= 5.95		
左側	〃 〃	3-2号集水桝～1-2号集水桝	L= 1.00		
横断	No. 5 + 16.50付近	1-3号集水桝～3号街渠桝	L= 8.61		
左側	〃 〃	3-2号集水桝～1-3号集水桝	L= 1.00		
左側	〃 〃	既設集水桝～3-2号集水桝	L= 13.79		
2号管渠					
Co台付き管 φ 400					7.60 m
右側	No. 1 + 0.00付近	5号街渠桝～3-3号集水桝	L= 1.85		
横断	No. 1 + 0.00付近	3-2号集水桝～5号街渠桝	L= 5.75		
3号街渠桝					
400×600×950					1.0 基
右側	No. 5 + 16.50付近		N= 1.0		
4号街渠桝					
400×600×850					1.0 基
右側	No. 3 + 16.01付近		N= 1.0		
5号街渠桝					
400×600×950					1.0 基
右側	No. 1 + 0.00付近		N= 1.0		
1-2号集水桝					
NK桝Ⅱ型	(300×300×H800)				2.0 基
右側	No. 7 + 19.36付近		N= 1.0		
左側	No. 3 + 16.01付近		N= 1.0		
1-3号集水桝					
NK桝Ⅱ型	(300×300×H1000)				1.0 基
左側	No. 5 + 16.50付近		N= 1.0		

排水構造物工 集計

種 別：排水構造物工
ブロック：
区 分：

細別／規格	算 式 ／ 図		数 量
3-2号集水桝 NK桝Ⅱ型 右側 左側 南側敷地 〃	(500×500×H1000) No. 6+ 4.03付近 No. 1+ 0.00付近 No. 3+16.01付近 No. 5+16.50付近	N= 1.0 N= 1.0 N= 1.0 N= 1.0	4.0 基
3-3号集水桝 NK桝Ⅱ型 右側 〃	(500×500×H1200) No. 3+16.01付近 No. 5+16.50付近	N= 1.0 N= 1.0	2.0 基
1号U型側溝 左側	No. 6+8 左側	L= 6.79	6.79 m
コンクリート 18N/mm2以上	0.195×6.79	= 1.324	1.324 m3
型枠 一般型枠	2.20×6.79	= 14.938	14.94 m2
基礎碎石 RC-40, t=150	0.70×6.79	= 4.753	4.75 m2
目地材 瀝青質目地材, t=10	1.324×1/10	= 0.132	0.13 m2
コンクリート蓋 C2-B300	6.79÷0.5	= 13.580	14.0 枚

・インバートコンクリート(市役所線)

かんたん側溝			計 算 式							単位	Co数量					
サイズ			高さ(m)		幅(m)		延長(m)									
市役所線(右側)																
W300	h	400	(	0.100	+	0.088	)	／	2	×	0.300	×	4.272	=	m ³	0.120
W300	h	600	(	0.082	+	0.075	)	／	2	×	0.300	×	1.329	=	m ³	0.031
W300	h	600	(	0.075	+	0.050	)	／	2	×	0.300	×	1.555	=	m ³	0.029
W300	h	700	(	0.150	+	0.117	)	／	2	×	0.300	×	2.000	=	m ³	0.080
W300	h	700	(	0.117	+	0.059	)	／	2	×	0.300	×	2.000	=	m ³	0.053
W300	h	800	(	0.159	+	0.055	)	／	2	×	0.300	×	12.302	=	m ³	0.395
W300	h	800	(	0.055	+	0.050	)	／	2	×	0.300	×	3.698	=	m ³	0.058
W300	h	900	(	0.150	+	0.136	)	／	2	×	0.300	×	10.074	=	m ³	0.432
W300	h	900	(	0.136	+	0.125	)	／	2	×	0.300	×	2.769	=	m ³	0.108
W300	h	900	(	0.125	+	0.113	)	／	2	×	0.300	×	2.399	=	m ³	0.086
W300	h	900	(	0.113	+	0.062	)	／	2	×	0.300	×	10.065	=	m ³	0.264
W300	h	1000	(	0.162	+	0.111	)	／	2	×	0.300	×	2.000	=	m ³	0.082
W300	h	1000	(	0.111	+	0.071	)	／	2	×	0.300	×	8.899	=	m ³	0.243
W300	h	1000	(	0.071	+	0.104	)	／	2	×	0.300	×	2.000	=	m ³	0.053
W300	h	1000	(	0.104	+	0.081	)	／	2	×	0.300	×	8.357	=	m ³	0.232
W300	h	1000	(	0.081	+	0.071	)	／	2	×	0.300	×	3.643	=	m ³	0.083
W300	h	1000	(	0.071	+	0.054	)	／	2	×	0.300	×	7.307	=	m ³	0.137
W300	h	1100	(	0.154	+	0.134	)	／	2	×	0.300	×	8.350	=	m ³	0.361
W300	h	1100	(	0.134	+	0.118	)	／	2	×	0.300	×	20.000	=	m ³	0.756
W300	h	1100	(	0.118	+	0.156	)	／	2	×	0.300	×	7.650	=	m ³	0.314
W300	h	1000	(	0.056	+	0.084	)	／	2	×	0.300	×	6.000	=	m ³	0.126
W300	h	1000	(	0.084	+	0.072	)	／	2	×	0.300	×	4.000	=	m ³	0.094
	h		(		+		)	／	2	×		×		=	m ³	0.000
市役所線(左側)																
W300	h	600	(	0.147	+	0.147	)	／	2	×	0.300	×	19.650	=	m ³	0.867
W300	h	600	(	0.147	+	0.150	)	／	2	×	0.300	×	3.757	=	m ³	0.167
W300	h	500	(	0.050	+	0.063	)	／	2	×	0.300	×	16.243	=	m ³	0.275
W300	h	500	(	0.063	+	0.100	)	／	2	×	0.300	×	15.757	=	m ³	0.385
W300	h	500	(	0.061	+	0.071	)	／	2	×	0.300	×	3.743	=	m ³	0.074
W300	h	500	(	0.071	+	0.141	)	／	2	×	0.300	×	20.768	=	m ³	0.660
W300	h	500	(	0.141	+	0.146	)	／	2	×	0.300	×	1.489	=	m ³	0.064
NK樹Ⅱ型																
3*3	h	800	(	0.050	+	0.050	)	／	2	×	0.300	×	0.300	=	m ³	0.010
3*3	h	1000	(	0.050	+	0.050	)	／	2	×	0.300	×	0.300	=	m ³	0.005
5*5	h	1000	(	0.050	+	0.050	)	／	2	×	0.500	×	0.500	=	m ³	0.052
5*5	h	1200	(	0.050	+	0.050	)	／	2	×	0.500	×	0.500	=	m ³	0.026
	h		(		+		)	／	2	×		×		=	m ³	0.000
W300	h	~900	t2 =	mm	底版底穴体積	0.00730	m ³ /製品	×	133.870	=	m ³			=	m ³	0.489
W300	h	1000~	t2 =	mm	底版底穴体積	0.00910	m ³ /製品	×	65.307	=	m ³			=	m ³	0.297
	h		t2 =	mm	底版底穴体積		m ³ /製品	×		=	m ³			=	m ³	0.000
W400	h	~1000	t2 =	mm	底版底穴体積	0.00730	m ³ /製品	×		=	m ³			=	m ³	0.000
W400	h	1100~	t2 =	mm	底版底穴体積	0.00910	m ³ /製品	×		=	m ³			=	m ³	0.000
	h		t2 =	mm	底版底穴体積		m ³ /製品	×		=	m ³			=	m ³	0.000
W500	h	1100~	t2 =	mm	底版底穴体積	0.01950	m ³ /製品	×		=	m ³			=	m ³	0.000
	h		t2 =	mm	底版底穴体積		m ³ /製品	×		=	m ³			=	m ³	0.000
W300	h		t2 =	mm	底版底穴体積	0.01090	m ³ /製品	×	12.899	=	m ³			=	m ³	0.070
W400	h		t2 =	mm	底版底穴体積	0.01090	m ³ /製品	×		=	m ³			=	m ³	0.000
W500	h		t2 =	mm	底版底穴体積	0.02340	m ³ /製品	×		=	m ³			=	m ³	0.000
	h		t2 =	mm	底版底穴体積		m ³ /製品	×		=	m ³			=	m ³	0.000
合 計												m ³	7.600			

212.076
212.076

1号U型側溝

号計算書

数 量 計 算 書

NO.

The drawing shows a cross-section of a concrete foundation. The top width is 600, divided into three sections of 150, 300, and 150. The top thickness is 80. The main body has a width of 600 and a height of 400. The base has a width of 700 and a thickness of 150. The total height is 550. The drawing includes labels for materials: C2-B300 for the concrete, concrete with a strength of $\sigma_{28} \geq 18 \text{ N/mm}^2$, and RC-40 for the base gravel. The drawing also shows a cross-section of a concrete slab with a width of 600 and a height of 110. The drawing includes dimensions for the concrete slab: 150, 300, 150, 80, 70, 70, 80, 110, 400, 150, 550, 50, 600, 700.

1.0m当り			
名 称・規 格	計 算 式	単 位	数 量
コンクリート 18N/mm2以上	$((0.6 \times 0.55) - (0.11 \times 0.44 + 0.3 \times 0.29)) \times 1.0 = 0.195$	m3	0.195
型枠 一般型枠	$0.55 \times 4 \times 1.0 = 2.200$	m2	2.20
基礎碎石 RC-40, t=150	$0.70 \times 1.0 = 0.700$	m2	0.70
目地材 瀝青質目地材, t=10	$0.195 \times 1/10 = 0.020$	m2	0.02
コンクリート蓋 C2-B300	$1.0 \div 0.5 = 2.000$	枚	2.0

1-2号集水树

号計算書

数 量 計 算 書

NO.

The diagram illustrates a drainage structure with the following details:


- Top View:** A square structure with an outer dimension of 500mm and an inner opening of 300mm. The structure is composed of a 100mm wide base, a 300mm wide central section, and a 100mm wide top flange. The total height is 500mm, with a 300mm section for the grate and a 100mm section for the base.
- Side View:** Shows the structure's profile with a total height of 860mm. The base is 600mm wide, and the top flange is 500mm wide. The structure is supported by a 100mm thick base layer. The grate is 300mm wide and 100mm high. The base layer is 100mm thick and made of concrete.
- Material Specifications:**
 - 底版コンクリート (Base Concrete): 18N/mm²以上
 - 基礎コンクリート (Foundation Concrete): 18N/mm²以上
 - 基礎砕石 (Foundation Gravel): RC-30
 - グレーチング (Grating): T-25 細目 (Fine Mesh)

1.0基当り			
名 称 ・ 規 格	計 算 式	単 位	数 量
プレキャスト樹 300×300×H800		基	1.0
基礎コンクリート 18N/mm2以上	0.600×0.600×0.050 = 0.018	m3	0.018
同上 型枠 均し	0.60×4×0.05 = 0.120	m2	0.12
基礎砕石 RC-30,t=100	0.60×0.60 = 0.360	m2	0.36
底版コンクリート 18N/mm2以上	”自由勾配側溝 インバートコンクリート”に含む		
グレーチング	T-25 細目	枚	1.0

1-3号集水樹

号計算書		数 量 計 算 書		NO.	
<					

3-2号集水枳



1.0基当り			
名 称 ・ 規 格	計 算 式	単 位	数 量
プレキャスト枳 500×500×H1000		基	1.0
基礎コンクリート 18N/mm ² 以上	0.800×0.800×0.100 = 0.064	m ³	0.064
同上 型枠 均し	0.80×4×0.10 = 0.320	m ²	0.32
基礎碎石 RC-30,t=100	0.80×0.80 = 0.640	m ²	0.64
底版コンクリート 18N/mm ² 以上	”自由勾配側溝 インバートコンクリート”に含む		
グレーチング	T-25 細目	枚	1.0

閉塞工 集計

種 別：閉塞工
ブロック：
区 分：

細別／規格	算 式／ 図	数 量
モルタル 1 : 3		1.1 m3
1号既設排水管 (φ 150)	$0.02\text{m}^2 \times 17.4\text{m} = 0.35$	
5号既設集水樹	$0.60\text{m} \times 0.60\text{m} \times 0.25\text{m} = 0.09$	
6号既設集水樹	$\pi \times 0.25\text{m} \times 0.25\text{m} \times 0.65\text{m} = 0.13$	
7号既設集水樹	$\pi \times 0.25\text{m} \times 0.25\text{m} \times 0.60\text{m} = 0.12$	
8号既設集水樹	$\pi \times 0.25\text{m} \times 0.25\text{m} \times 0.67\text{m} = 0.13$	
9号既設集水樹	$1.00\text{m} \times 1.00\text{m} \times 0.27\text{m} = 0.27$	

平面図

1号既設排水管
φ 150

モルタル充填
A=0.02m²

5号既設集水樹

モルタル充填

6号既設集水樹

モルタル充填

7号既設集水樹

モルタル充填

8号既設集水樹


モルタル充填

9号既設集水樹

モルタル充填

舗装工 集計

種 別：舗装工
ブロック：
区 分：

細別／規格	算 式 ／ 図	数 量
1号車道舗装（現況復旧）		
〔1.0式当たり〕 表層 再生密粒度As, t=50	舗装平面図より	352.5 m ²
下層路盤 RC-30, t=100	//	352.5 m ²
 表層(再生密粒度As) t=5cm プライムコート (1.2L/m²程度) 下層路盤(RC-30) t=10cm		
舗 装 平 面 図		







構造物撤去工 作業土工 集計

種 別：作業土工
 ブロック：
 区 分：

細別／規格	算 式 / 図	数 量
作業土工 床掘 土砂 本線 3号既設排水管 (φ 900) 6号既設集水桝 7号既設集水桝 8号既設集水桝 9号既設集水桝	$\begin{aligned} & \text{土積計算書より} & = 71.2 \\ & 2.64\text{m}^2 \times 5.9\text{m} + 2.79\text{m}^2 \times 8.0\text{m} & = 37.9 \\ & (1.10\text{m} \times (1.00\text{m} \times 1.00\text{m} + 1.00\text{m} \times 2.10\text{m} + 2.10\text{m} \times 2.10\text{m}) \div 3) - (0.65\text{m} \times 0.65\text{m} \times 1.10\text{m}) & = 2.3 \\ & (1.10\text{m} \times (1.00\text{m} \times 1.00\text{m} + 1.00\text{m} \times 2.10\text{m} + 2.10\text{m} \times 2.10\text{m}) \div 3) - (0.65\text{m} \times 0.65\text{m} \times 1.10\text{m}) & = 2.3 \\ & (1.10\text{m} \times (1.00\text{m} \times 1.00\text{m} + 1.00\text{m} \times 2.10\text{m} + 2.10\text{m} \times 2.10\text{m}) \div 3) - (0.65\text{m} \times 0.65\text{m} \times 1.10\text{m}) & = 2.3 \\ & (1.85\text{m} \times (1.80\text{m} \times 1.80\text{m} + 1.80\text{m} \times 3.65\text{m} + 3.65\text{m} \times 3.65\text{m}) \div 3) - (1.40\text{m} \times 1.40\text{m} \times 1.85\text{m}) & = 10.6 \end{aligned}$	126.6 m3
埋戻し 最大埋戻し幅1m以上4m未満 3号既設排水管 (φ 900) 9号既設集水桝	$\begin{aligned} & \text{外構部} \quad 3.64\text{m}^2 \times 8.0\text{m} & = 29.1 \\ & 1.85\text{m} \times (1.80\text{m} \times 1.80\text{m} + 1.80\text{m} \times 3.65\text{m} + 3.65\text{m} \times 3.65\text{m}) \div 3 & = 14.3 \end{aligned}$	43.4 m3
路床盛土 B<2.5 本線 6号既設集水桝 7号既設集水桝 8号既設集水桝 路床盛土 2.5≤B<4.0 3号既設排水管 (φ 900)	$\begin{aligned} & \text{土積計算書より} & = 64.5 \\ & (1.00\text{m} \times (1.00\text{m} \times 1.00\text{m} + 1.00\text{m} \times 2.00\text{m} + 2.00\text{m} \times 2.00\text{m}) \div 3) & = 2.3 \\ & (1.00\text{m} \times (1.00\text{m} \times 1.00\text{m} + 1.00\text{m} \times 2.00\text{m} + 2.00\text{m} \times 2.00\text{m}) \div 3) & = 2.3 \\ & (1.00\text{m} \times (1.00\text{m} \times 1.00\text{m} + 1.00\text{m} \times 2.00\text{m} + 2.00\text{m} \times 2.00\text{m}) \div 3) & = 2.3 \\ & \text{車道部} \quad 2.24\text{m}^2 \times 5.9\text{m} & = 13.2 \end{aligned}$	71.4 m3 13.2 m3
路体盛土 B<2.5 3号既設排水管 (φ 900)	$\text{車道部} \quad 0.97\text{m}^2 \times 5.9\text{m} = 5.7$	5.7 m3

構造物撤去工 作業土工 集計

種 別：作業土工
ブロック：
区 分：

細別／規格	算 式 ／ 図	数 量
作 業 土 工 根 拠 図		
3号既設排水管 (φ 900) 車道部、L=5. 9m	 床掘り 2. 64 路床盛土 2. 24 路体盛土 0. 97	
3号既設排水管 (φ 900) 外構部、L=8. 0m	 床掘り 2. 79 埋戻し 3. 64	
6号既設集水樹 2100×2100 2000×2000	 床掘り 路床盛土	
7号既設集水樹 2100×2100 2000×2000	 床掘り 路床盛土	
8号既設集水樹 2100×2100 2000×2000	 床掘り 路床盛土	
9号既設集水樹 3650×3650	 床掘り 埋戻し	

撤去工 作業土工

測 点	点間距離 (m)	床掘り						路床盛土						備 考
		土砂						B<2.5m						
		断 面	平 均	数 量				断 面	平 均	数 量				
No. 1 + 5.638	—	0.9	—	—				0.8	—	—				No. 2流用
No. 2	14.362	0.9	0.90	12.9				0.8	0.80	11.5				
No. 3	20.000	0.7	0.80	16.0				0.6	0.70	14.0				
No. 4	20.000	0.6	0.65	13.0				0.6	0.60	12.0				
No. 5	<u>19.896</u>	0.6	0.60	11.9				0.5	0.55	10.9				
No. 6	<u>27.521</u>	0.5	0.55	15.1				0.5	0.50	13.8				
No. 6 + 2.144	<u>4.582</u>	0.5	0.50	2.3				0.5	0.50	2.3				No. 6流用
※下線付き点間距離は平面図CAD計測														
合 計	m 106.361			m3 71.2						m3 64.5				

構造物撤去工 集計

種 別 :
 ブロック :
 区 分 :

細別／規格	算 式 / 図	数 量
鋼製蓋 撤去 500×500	撤去平面図より	3 枚
マンホール蓋 撤去 φ 500 φ 1000	撤去平面図より 〃	1 枚 1 枚
コンクリート取壊し 無筋		29.5 m3
本線(既設道路側溝)	計算書より	= 26.70
1号既設排水路(270×350)	$0.28\text{m}^2 \times 0.8\text{m}$	= 0.22
2号既設排水路(270×360)	$0.28\text{m}^2 \times 3.3\text{m}$	= 0.92
1号既設集水樹	$(0.7\text{m} \times 0.7\text{m} \times 1.265\text{m}) - (0.4\text{m} \times 0.4\text{m} \times 1.0\text{m})$	= 0.46
2号既設集水樹	$(0.71\text{m} \times 0.71\text{m} \times 1.14\text{m}) - (0.4\text{m} \times 0.4\text{m} \times 0.87\text{m})$	= 0.44
3号既設集水樹	$(0.75\text{m} \times 0.75\text{m} \times 1.195\text{m}) - (0.58\text{m} \times 0.58\text{m} \times 0.945\text{m})$	= 0.35
4号既設集水樹	$(0.7\text{m} \times 0.7\text{m} \times 1.23\text{m}) - (0.4\text{m} \times 0.4\text{m} \times 0.96\text{m})$	= 0.45
鉄筋		9.1 m3
2号既設排水管(φ 300)	$0.03\text{m}^2 \times 103.6\text{m}$	= 3.11
3号既設排水管(φ 900)	$0.21\text{m}^2 \times 13.9\text{m}$	= 2.92
5号既設集水樹	$(0.9\text{m} \times 0.9\text{m} \times 1.15\text{m}) - (0.6\text{m} \times 0.6\text{m} \times 1.15\text{m})$	= 0.52
6号既設集水樹	$(0.65\text{m} \times 0.65\text{m} \times 1.15\text{m}) - (\pi \times 0.25\text{m} \times 0.25\text{m} \times 1.15\text{m})$	= 0.26
7号既設集水樹	$(0.65\text{m} \times 0.65\text{m} \times 1.15\text{m}) - (\pi \times 0.25\text{m} \times 0.25\text{m} \times 1.15\text{m})$	= 0.26
8号既設集水樹	$(0.65\text{m} \times 0.65\text{m} \times 1.15\text{m}) - (\pi \times 0.25\text{m} \times 0.25\text{m} \times 1.15\text{m})$	= 0.26
9号既設集水樹	$(1.4\text{m} \times 1.4\text{m} \times 1.85\text{m}) - (1.0\text{m} \times 1.0\text{m} \times 1.85\text{m})$	= 1.78

1号既設排水路
270×350

A=0.28m²

2号既設排水路
270×360

A=0.28m²

1号既設集水樹
No. 5+6付近

A=0.28m²

2号既設集水樹
No. 3+17付近

A=0.28m²

3号既設集水樹
No. 3+5付近

A=0.35m²

4号既設集水樹
No. 2+7付近

A=0.45m²

2号既設排水管
φ 300

A=0.03m²

3号既設排水管
φ 900

A=0.21m²

5号既設集水樹
No. 1+10付近

A=0.52m²

6号既設集水樹
No. 1+3付近

A=0.26m²

7号既設集水樹
No. 0+10付近

A=0.26m²

8号既設集水樹
No. 0+6付近

A=0.26m²


9号既設集水樹
鳴門市役所敷地内

A=1.78m²

: コンクリート取壊し

構造物撤去工 集計

種 別 :
ブロック :
区 分 :



構造物撤去工 集計

種 別 :
ブロック :
区 分 :

細別／規格	算 式 ／ 図		数 量
As舗装版 取壊し t=50 車道	根拠図より	= 340.9	340.9 m2
As舗装版 切断 t=50 車道	根拠図より	= 358.3	358.3 m
根 拠 図			
搬運 Co殻 無筋 鉄筋 As殻	t=50	$340.9\text{m}^2 \times 0.05$	= 17.0
			29.5 m3 9.1 m3 17.0 m3

撤去工

測点	点間距離 (m)	コンクリート取壊し									備考
		無筋									
		断面	平均	数量							
No. 1 + 9.980	—	0.2	—	—							No. 2流用
No. 2	10.020	0.2	0.20	2.0							
No. 3	20.000	0.2	0.20	4.0							
No. 4	20.000	0.4	0.30	6.0							
No. 5	20.000	0.2	0.30	6.0							
No. 6	20.000	0.2	0.20	4.0							
No. 7	20.000	0.2	0.20	4.0							
No. 7 + 3.730	3.730	0.2	0.20	0.7							No. 7流用
合計	m 113.750			m ³ 26.7							